



FINISHED INTERIOR

- ENGINEERED TRUSS 4' O.C.
- 4/12 PITCH
- 1/4" DOW INS.
- 29 GA. ROOF METAL
- 2x4 ROOF PURLINS 24" O.C.
- 2x12 HEADERS ON BOTH SIDES OF POST
- 6-4" POLE BARN SPIKES ON EACH SIDE
- 29 GA. WALL METAL
- 2x4 WALL NAILERS 2'-0" ON CENTER
- 6"x6" TREATED POST
- 2 ROWS 2x6 T&G TREATED FINISH GRADE
- 4"x12" DIA. PRECAST CONCRETE PAD

48'x120'x16' POLE BARN

<p>THE WORCH LUMBER CO. 937-526-4501 FAX 937-526-3229</p>		DWG. No. 48x120x16 POLE BARN
		DATE: 2-2-12
DRAWN: ADAM		MOBILE #
SCALE: NO SCALE		SHT.: 1 OF: 1